Abstract Notification dated 19th September 1938.

The attention of the public is hereby invited to the detailed notification, inviting sealed tenders for Restoring the breached Manigenahalli Tank, Register No. 89 of Magadi Taluk, published on pages 1645—1647 of Part VI of the *Mysore Gazette*, dated 22nd September 1938.

2. The last date for the receipt of the tender is 2 P.M. on 18th October 1938. Duplicate challan for having credited the deposit amount of Rs. 170 into the treasury under "17 (*a*) P. W. Deposits," must accompany each tender.

N. LAKSHMINARASIMHAIYA,
Executive Engineer.

BUILDINGS DIVISION, BANGALORE.

Notification dated 26th September 1938.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Buildings Division, upto 20th October 1938, upto 2 P.M. for constructing two blocks of coolies' quarters in Government Porcelain Factory, Bangalore. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of May 1939.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Buildings Division, between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 260, in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for constructing two blocks of coolies' quarters in Government Porcelain Factory, Bangalore," in default of which tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond, in default of which his tender will be considered cancelled and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Executive Engineer's Office in due course. No enquiry regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. Rates once tendered will not be enhanced on any account.

10. Rates for non-tendered and non-estimated items shall be as per schedule rates of the Department or those fixed by the Executive Engineer after working out data with not more than 10 per cent for contractor's profit.

11. In all matters not specifically provided for and in all matters of dispute about rates, quantities, measurements, quality of works, etc., and in all disputes of any kind, the decision of the Executive Engineer will be final and legally binding.

12. Tender must be given in words as well as in figures and they must be in specific term of unit shown against each item of work. Any quotation quoted at so much percentage less or more than the estimated rate will not be accepted.

Tender for constructing two Blocks of Coolies' Quarters in Government Porcelain Factory, Bangalore.

Sl. No.	Items of work	Unit	Rate	Quantity	Rate to be quoted
			Rs. a. p.		
1	Earthwork Excavation for foundation and filling in basement	C.yd.	0 3 0	111	
2	Granite jelly concrete in lime mortar	C.ft.	0 3 0	949	
3	Size stone in clay	"	0 3 3	2,036	
4	Burnt stone slabs 6" thick roughly dressed and fixed	S.ft.	0 4 0	80	
5	Burnt brick in mud in superstructure	C.ft.	0 3 0	3,416	
6	Teakwood door frames 3"×4½", shutters ¾" thick battened and brazed with iron fittings complete (Mysore teak)	S.ft.	1 4 0	120	
17	Teakwood window frame 3"×4", shutters ¾" thick battened with ¼" iron bars and iron fittings, etc., complete (Mysore teak)	S.ft.	1 6 0	120	

Serial No.	Items of work	Unit	Rate	Quantity	Rate to be quoted
			Rs. a. p.		
8	Mysore teakwood wrought and put up with wood oiling	C.ft.	4 8 0	75·00	
9	Roofing with first class Mangalore tiles over 2" × 1" teak reaper, etc., complete	Sqr.	20 0 0	1,690	
10	Mangalore ridge tiles set in mortar	R.ft.	0 5 0	65	
11	Lime mortar plastering, two coats	Sqr.	3 0 0	70·04	
12	White and colour washing as per plastering ..	,,	0 4 0	70·04	
13	Lac Factory green painting	,,	3 8 0	4·80	
14	Cement pointing to basement	,,	3 0 0	1·82	
15	Flooring with cement concrete 1½" thick over 3" lime concrete with nice cement finish at top, etc.	Sq.	18 0 0	10·08	
16	Mortar band over roof at ends	R.ft.	0 4 0	52	
17	Burnt stone slabs 6" thick, one line dressed and fixed for steps	S.ft.	0 5 0	32	
18	Constructing a sink in kitchen	No.	5 0 0	4	

N.B.—Quantity given above is only for one block. Two blocks are to be constructed.

Notification dated 26th September 1938.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Buildings Division, upto 19th October 1938, 2 P.M., for constructing three Officers' quarters in Government Porcelain Factory, Bangalore. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of April 1939.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Bangalore, between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of rupees four hundred (Rs. 400) only in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for constructing three Officers' quarters in Government Porcelain Factory, Bangalore," in default of which tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond, in default of which his tender will be considered cancelled and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Executive Engineer's Office, in due course. No enquiry regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. Rates once tendered will not be enhanced on any account.

10. Rates for non-tendered and non-estimated items shall be as per schedule rates of the department or those fixed by the Executive Engineer after working out data with not more than 10 per cent for contractor's profit.

11. In all matters not specifically provided for and in all matters of dispute about rates, quantities, measurements, quality of works, etc., and in all disputes of any kind, the decision of the Executive Engineer will be final and legally binding.

12. Tenders must be given in words as well as in figures and they must be in specific term of unit shown against each item of work. Any quotation quoted at so much percentage less or more than estimated rate will not be accepted.

Tender for constructing three Officers' Quarters in Government Porcelain Factory, Bangalore.

Sl. No.	Items of work	Unit	Rate Rs. a. p.	Quantity	Rate to be quoted
1	Earthwork excavation for foundation and filling in basement including watering, tamping, etc., complete	C.yd.	0 3 0	82	
2	Lime mortar stone jelly concrete 1 : 2 including tamping, etc., complete	C.ft.	0 3 0	498	
3	Size stone in clay for foundation and basement including bond slabs at 6' apart, etc., complete	C.ft.	0 3 3	1,334	
4	Burnt stone slabs 6" thick, one line dressed on all faces and fixed in mortar for basement slabs	S.ft.	0 5 6	348	
5	Burnt brick in clay for superstructure with necessary bond stones complete	C.ft.	0 3 0	2,061	
6	Burnt brick in mortar	C.ft.	0 4 0	419	
7	Burnt stone slabs 6" thick roughly dressed and fixed in mortar	S.ft.	0 4 0	139	
8	Providing and fixing teakwood doors 3" × 4½" frame fully panelled 1" thick shutters with iron fittings bolts, hinges, etc., complete	S.ft.	1 4 0	257	
9	Teakwood windows 3" × 4½" frame fully panelled on outisde 1" thick shutters with iron bars, hinges, etc., complete	S.ft.	1 6 0	173	
10	R. C. perforated ventilator pannels as per design	S.ft.	0 8 0	45	
11	Burnt brick in mortar pillar as per design	C.ft.	0 4 0	61	
12	R. B. C. Terrace to take a total load of 1½ Cwt. with 3" surkey concrete 2 rows of flat tiles, 1" thick lime mortar (1:2) plastering on top and bottom, etc., complete as per specification	Sqr.	60 0 0	1·32	
13	Teakwood wrought and put up including wood oiling, etc., complete (Mysore teak)	C.ft.	4 8 0	54·88	
14	Mangalore tiles roofing on 1" × 2" reapers, etc., complete	Sq.	20 0 0	13·70	
15	Ridge tiles set in cement mortar, etc., complete	R.ft.	0 5 0	33	
16	Plain parapet wall 1½' high as per design	R.ft.	0 10 0	33	
17	Cornice as per design	,,	0 6 0	33	
18	Mortar band over roof	,,	0 3 0	100	
19	Lime mortar plastering	Sq.	3 0 0	57·26	
20	White and colour washing as per plastering	,,	0 4 0	57·26	
21	Flooring with ½" cement concrete over 3" of lime concrete finished with red ochre or red cement plaster ½" thick with cut lines, etc., complete	Sq.	18 0 0	8·34	
22	Pointing to basement with cement mortar with cut lines, etc., complete	,,	2 12 0	2·10	
23	Painting to doors and windows with Government Lac Factory green paint, two coats	Sq.	3 8 0	10·85	
24	Constructing chimney and sink in bath and kitchen	L. S.	..	..	

N.B.—Quantity given above is only for one Quarter. Three Quarters are to be constructed.

Notification dated 26th September 1938.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Buildings Division, upto 18th October 1938, upto 2 P.M. for constructing an Electro-tunnel kiln in the Government Porcelain Factory, Bangalore. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of May 1939.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Buildings Division, between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 1,700 in cash or Government Promissory Notes, as earnest money, and be superscribed " Tender for constructing and Electro-tunnel kiln in Government Porcelain Factory, Bangalore, in default of which tenders will be rejected.

5. The final acceptance of any tender will rest with the Superintending Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Executive Engineer's Office in due course. No enquiry regarding the acceptance or rejection of a tender will receive any reply

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. Rates once tendered will not be enhanced on any account.

10. Rates for non-tendered and non-estimated items shall be as per schedule rates of the department or those fixed by the Executive Engineer after working out data with not more than 10 per cent for contractor's profit.

11. In all matters not specifically provided for and in all matters of dispute about rates, quantities, measurements, quality of works, etc., and in all disputes of any kind, the decision of the Executive Engineer will be final and legally binding.

12. Tender must be given in words as well as in figures and they must be in specific term of unit shown against each item of work. Any quotation quoted at so much percentage less or more than estimated rate will not be accepted.

Tender for constructing an Electro-funnel Kiln in Government Porcelain Factory, Bangalore.

Serial No.	Items of work	Unit	Rate	Quantity	Rate to be quoted
			Rs. a. p.		Rs.
1	*Earthwork.*—Excavation for foundation and filling in basement	C.ft.	0 3 0	902	
2	Granite jelly concrete in lime mortar	,,	0 3 6	4,156	
3	Size stone in lime mortar with bond stones at 6' apart in each course complete	C.ft.	0 4 0	19,149	
4	Burnt brick in lime mortar in superstructure	,,	0 4 6	18,612	
5	Burnt stone slabs 6" thick one line dressed on exposed portions and set in mortar	S.ft.	0 5 0	2,350	
6	Burnt stone slabs 6" thick roughly dressed and fixed for lintels of doors and windows	S.ft.	0 4 6	822	
7	Burnt stone slabs 2 lines dressed and fixed for steps	S.ft.	0 6 6	288	
8	(*a*) Mysore teakwood doors with 1½" shutters (panelled) with complete iron fittings, etc., with clamps	S.ft.	1 4 0	728	
	(*b*) Mysore teakwood semi-circular fan lights above big doors	S.ft.	1 8 0	50	
9	Mysore teakwood windows with glazed shutters 4 leaves, 1¼" thick with iron fittings etc., complete as per approved design	S.ft.	1 4 0	2,688	
10	Mild steel trusses for a span of 30 feet clear including hoisting, fixing, etc., complete	Cwt.	14 0 0	252	
11	Tata's tested steel girders for lintels over big doors of 8' span	Cwt.	14 0 0	7.5	
12	Mysore teakwood wrought and put up with two coats of wood oiling, etc., complete	C.ft.	4 8 0	919	
13	Mangalore tiled roofing with 1st class Mangalore tiles on teak reepers 1"×2" with wood oiling, etc., complete	Sqr.	20 0 0	191.74	
14	Lime mortar plastering	,,	3 0 0	277.15	
15	White-washing 2 coats as per plastering	,,	0 4 6	277.15	
16	Cement pointing to basement alround	,,	2 12 0	23.90	
17	Flooring with 1½" cement concrete over 3" lime concrete with nice coloured cement finish at top, etc., complete	Sqr.	18 0 0	134.40	
18	Providing and fixing pendents and finials	No.	0 8 0	6	
19	Mangalore ridge tiles set in cement mortar	R.ft.	0 6 0	436	
20	Mortar hand over roof	,,	0 4 0	57	
21	Painting to doors and windows with 2 coats of Government Lac Factory green painting	Sqr.	4 0 0	42.44	
22	Cement concrete for fixing anchor bolts of trusses	C.ft.	0 10 0	1,134	
	(*a*) Boxing girders with burnt brick in cement mortar	R.ft.	0 8 0	20	
23	Mysore teakwood Eaveboard 9" wide ¾" thick including fixing, etc., complete	R.ft.	0 8 0	972	

Notification dated 26th September 1938.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Buildings Division, up to Monday the 17th October 1938, up to 2 P.M. for extending second floor of Government State Life Insurance Office Building, Bangalore. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of June 1939.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 1,150 (one thousand one hundred and fifty) in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for extending second floor of Government State Life Insurance Office Building, Bangalore," in default of which tenders will be rejected.

5. The final acceptance of any tender will rest with the Superintending Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond, in default of which his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Executive Engineer's Office in due course. No enquiry regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. Rates once tendered will not be enhanced on any account.

10. Rates for non-tendered and non-estimated items shall be as per schedule rates of the department or those fixed by the Executive Engineer after working out data with not more than 10 per cent for contractor's profit.

11. In all matters not specifically provided for and in all matters of dispute about rates, quantities, measurements, quality of works, etc., and in all disputes of any kind, the decision of the Executive Engineer will be final and legally binding.

12. Tenders must be given in words as well as in figures and they must be in specific term of unit shown against each item of work. Any quotation quoted at so much percentage less or more than estimated rate will not be accepted.

Tenders for extending Second Floor of Government Life Insurance Office Building, Bangalore.

Serial No.	Items of work	Unit	Rate	Quantity	Rate to be quoted
			Rs. a. p.		
1	Burnt brick in lime mortar	C.ft.	0 5 6	3,370	
2	Wire-cut brick in lime mortar pillars with caps and bases including bond slabs at intervals of 3 feet height	C.ft.	1 8 0	265	
3	Burnt stone slabs 6" thick one line dressed for sills of windows and stone plates below R. C. C. roof	S.ft.	0 6 0	410	
4	Burnt brick in lime mortar arch work	C.ft.	0 5 6	258	
5	Plastering with chunam mortar for walls including rounding off all projecting corners and with convex corners having cement mortar 1 : 4 for a width of 3" both sides	Sqr.	4 0 0	77.44	

Serial No.	Items of work	Unit	Rate	Quantity	Rate to be quoted
			Rs. a. p.		
6	White and colour washing two coats	Sq.	0 6 0	77.44	
7	Tested rolled steel girders as per B. S. S. including lifting and hoisting and boxing with cement mortar and terrace brick reinforced with galvanized wire netting alround, with one coat of anti-corrosive painting and fixing with cement concrete in walls	Cwt.	14 0 0	58½	
8	Roofing with reinforced concrete terrace 1 : 2 : 4 5½" thick with ceiling pillastered as per design and to carry a super load of 50 lbs. per S. ft. and on top with surki concrete 4" thick with 2 coats of flat tiles and plastered smooth on top ..	Sqr.	75 0 0	23.87	
9	Fixing steel trusses on bed plates with bolts and nuts	Cwt.	14 0 0	15	
10	Teakwood wrought and put up with wood oiling ..	C.ft.	5 0 0	72.46	
11	Roofing with first class Mangalore tiles on teak reepers including nailing and wood oiling, etc., complete	Sqr.	28 0 0	12.96	
12	Setting ridge tiles in lime mortar and painted with cement	R.ft.	0 12 0	48	
13	Removing present plastering on top of present terrace and putting cement concrete 1 : 2 : 4 2" thick with toping of red cement ¾" thick finished smooth and laid in squares of about 6'×6' with aluminium strips at joints and cut to tile pattern with all corners rounded ..	Sqr.	30 0 0	30.04	
14	Skirting of ½" thick cement concrete 1 : 2 : 4 with topping of coloured cement ¼" thick 9" high for walls as per design	R.ft.	0 2 6	266	
15	Cement perforated slabs as per design in parapet wall of verandah 1½" thick with 2" thick 2" wide frame alround 1 per cent reinforced neatly finished	S.ft.	1 4 0	190	
16	Balustrated parapet wall 2½' high as per design with plastering, etc., complete between pillars of verandah	S.ft.	2 12 0	143	
17	Plain parapet wall 1½' high 9" thick with plastering, etc., complete as per design	R.ft.	0 12 0	67	
18	Ornamental cornice as per design in the existing building, i.e., 9" deep 9" projection including plastering, etc., complete	R.ft.	1 2 0	250	
19	Chunam borders over the ends of gables 9"×6" including plastering, etc., complete	R.ft.	0 4 0	54	
20	Teakwood doors with frames 3"×5" without bottom sills having ⅓ panelled ⅔ glazed (Pilkington's pir headed ⅛") 1½" thick shutters including Acme brass fittings rim door locks with handles 3 finger plate 12"×4" as per design with six inches brass hinges 2 six inches hooks, brass screws, barrel bolts of suitable size, etc., with semicircular ventilators above including Dulux varnish 2 coats	S.ft.	2 0 0	230	
21	Teakwood windows 3"×5" frame with 1½" thick glazed shutters opening out side in four halves with semicircular ventilators at top including iron bars ¾" diam., 4" apart brass hinges, hooks, 2" ring and casement adjusting stays, etc., complete including 2 coats of Dulux varnish ..	S.ft.	2 4 0	510	
22	C. I. rain water down pipes of 4" diameter with suitable bends, etc., complete	R.ft.	2 0 0	300	
23	Dismantling present parapet wall of first floor roof	L. S.			

N.B. Quantities given in the above is for one wing only.

B. R. GARUDACHAR,
Executive Engineer.